TECHNICAL SPECIFICATION SHEET

iKONIC JUPITER

MRL CANTILEVER

ikjup1000

iKONIC LIFTS
Sophisticated Lift Thinking

CORE FEATURES INCLUDE:

- Machine room-less configuration
- High efficiency gear-less drive system
- Two **BREEAM** credits available
- Smooth and quiet ride quality
- Full Equality Act (**EN81-70**) compliance
- Automatic emergency operation

SUITABLE FOR:



TECHNICAL FEATURES	
LIFT TYPE	Passenger
LIFT MODEL	ikjup1000
STANDARDS	BS EN 81-20/50 BS EN 81-21 BS EN 81-28 BS EN 81-58 BS EN 81-70 BS EN 81-71 BS EN 81-72 BS EN 81-73
MAX DUTY LOAD (Kg)	1000
RATED SPEED (m/s)	<1.0
STARTS PER HOUR	240
MAX LIFT TRAVEL (M)	45
PIT (mm)	1200*
HEADROOM (mm)	3600*
POWER SUPPLY (TNP)	400 V 3 Phase 50 Hertzs
DRIVE SYSTEM	Geared Traction MRL
ENTRANCE OPTIONS	Single entrance, Through entrance or Adjacent
USAGE SUITABILITY	Medium
CONTROL SYSTEM	Automatic Push
LEVELLING ACCURACY	In accordance with EN81
CAR DOOR	Centrally or Side Opening
LANDING DOOR	Centrally or Side Opening
CLEAR OPENING (mm)	From 700
FIRE RATING	120 mins in accordance with BS EN 81-58
DOOR SAFETY	Full height non-contact electronic safety light curtain
ARCHITRAVES	Slim line entrance frames

*Dependant upon lift speed &, or load capacity contact ikonic lifts for details

iKONIC Lifts Ltd
Telephone: 0203 376 6440 *E-mail:* sales@ikoniclifts.co.uk
Company Number: 11365265 **www.ikoniclifts.co.uk**

TECHNICAL SPECIFICATION SHEET

iKONIC JUPITER

MRL CANTILEVER

ikjup1000

iKONIC LIFTS
Sophisticated Lift Thinking

FINISHES SUPPLIED AS STANDARD FOR ikjup1000	
WALL	Decorative panels*
FLOOR	Non-slip vinyl or studded rubber selected from our standard range*
MIRROR	Half height, full width located on the rear wall*
HANDRAIL	Tubular stainless steel, located on the side wall opposite car station*
CEILING	Decorative white panels with flush mounted LED spot lighting incorporation emergency lift selected from our standard range*
CAR STATION	Stainless steal*
CAR DOORS	Stainless steal*
LANDING DOORS	Stainless steal*
LANDING ARCHITRAVES	Stainless steal*
CONTROLLER CABINET	At the landing entrance*
LANDING DOORS	Stainless steal*
LANDING FACE PLATE	Stainless steal*

INDICATORS SUPPLIED AS STANDARD FOR ikjup1000	
CAR PUSH BUTTONS	Full set of pushes in car station 400mm from the door face*
EMERGENCY COMMUNICATION	Automatic dialling emergency telephone activated upon pressing alarm push*
LANDING PUSHES	Micro movement illuminating pushes, tactile legends complaint with EN81-70*
LANDING INDICATORS	Direction arrows located above door on all landings. Position indicator at main landing*
FEATURES	• Full set of car pushes • Position indicator • Door open button • Alarm • Voice Synthesiser • Overload Indicator

**We have an extensive range of finishes and indicators any changes requested will be stated in your quotation for actual finishes.*

SHAFT & MACHINE ROOM FOR ikjup1000	
SHAFT CONSTRUCTION	Construction by the main contractor to meet the load and in accordance with iKONIC Lifts requirements
PIT PROP	Included
MACHINE ROOM LOCATION	Controller located in front wall at top floor, as standard other options available.
PIT LADDER	Included
NOTICES	Electric shock, hand lowering
CONTROLLER MAT	Voltage rated rubber mat included
PIT SOCKET OUTLET	Included
MAINTENANCE SAFETY BARRIER	Fitted to the top of lift car

12 MONTH WARRANTY FOR ikjup1000
INCLUDED- Subject the lift being maintained by ISO 9001 approved lift service company in accordance with our recommendations

12 MONTH SERVICING FOR ikjup1000
Service contracts available on request. Contact our service department for a free quotation **service@ikoniclifts.co.uk**

ADDITIONAL ITEMS INCLUDED NOT INCLUDED FOR ikjup1000			
INCLUDED		**NOT INCLUDED**	
DOCUMENTATION	General Arrangement Drawings Technical Manual Health & Safety Documentation Method & Risk Assessments	GUIDE FIXINGS	To be supplied and installed into a suitable constructed shaft by main contractor
LIFT DELIVERY	Our offer will include delivery to site a fork lift truck with a driver will need to be provided by the contractor. The off loading area suitable for storage needs to be on the same level and adjacent to the lift shaft.	SCAFFOLDING	To be installed by main contractor in accordance with the requirements specified by iKONIC LIFTS
INSTALLATION	Included	SHAFT CONSTRUCTION	To be constructed by the main contractor
COMMISSIONING	Included	SHAFT PAINTING	To be completed by the main contractor
		LIFTING BEAMS	To be supplied and tested by the main contractor
		SHAFT LIGHTING	To be supplied and tested by the main contractor

iKONIC Lifts Ltd
Telephone: 0203 376 6440 *E-mail:* sales@ikoniclifts.co.uk
Company Number: 11365265 **www.ikoniclifts.co.uk**